



**Code for Facilities, Technology, Inspection,
Safety Diagnosis and Safety Assessment for
Filling of LP Gas in Small Cylinders**

Personnel

Gas Technical Standards Committee

Chairman	Kwang-Won Lee, Professor of Hoseo University
Vice-Chairman	Seung-Hoon Nam, Principal Researcher of KRISS
Ex Officio Member	Hui-Won Lee, Manager of Energy Safety Department, Ministry of Trade, Industry & Energy Hae-Myeong Yang, Director of Technology and Safety, Korea Gas Safety Corporation
High-Pressure Gas	Seung-Hoon Nam, Principal Researcher of KRISS Beom-Seok Lee, Principal Professor of Kyung Hee University Dong-Myeong Ha, Professor of Semyung University Chang-Gi Kim, Principal Researcher of Korea Institute of Machinery and Materials Hyuk-Myun Kwon, Director General of Occupational Safety & Health Research Institute Su-Dong Byun, CEO of Q-Best
Liquefied Petroleum Gas	Doo-Seon Park, Managing Director of Daesung Industrial Gas Co., Ltd Hyeong-Hwan Ann, Professor of Korea National University of Transportation Byeong-Hak Choei, Professor of Gangneung-Wonju National University Seong-Min Lee, Director of KOGAS Research Institute Yong-Gwon Lee, Vice-President of EG CNE Co.,Ltd Gi-hyeon Jang, Director of Kiturmi Jeong-Sik Chon, Direto of E1 CO., Ltd.

History of Establishment and Revision of KGS Code	
Code Number	KGS FP334 ²⁰¹⁹
Code Title	Code for Facilities, Technology, Inspection, Safety Diagnosis and Safety Assessment for Filling of LP Gas in Small Cylinders

Date of Establishment/Revision	Description
December 31, 2008	Established (Notification of the Ministry of Knowledge Economy No. 2008-380)
December 2, 2009	Revised (Notification of the Ministry of Knowledge Economy No. 2009-454)
January 3, 2011	Revised (Notification of the Ministry of Knowledge Economy No. 2010-489)
July 27, 2011	Revised (Notification of the Ministry of Knowledge Economy No. 2011-369)
June 26, 2012	Revised (Notification of the Ministry of Knowledge Economy No. 2012-313)
May 20, 2013	Revised (Notification of the Ministry of Trade, Industry & Energy No. 2013-087)
June 27, 2013	Revised (Notification of the Ministry of Trade, Industry & Energy No. 2013-136)
October 31, 2013	Revised (Notification of the Ministry of Trade, Industry & Energy No. 2013-308)
October 6, 2014	Revised (Notification of the Ministry of Trade, Industry & Energy No. 2014-510)
November 17, 2014	Revised (Notification of the Ministry of Trade, Industry & Energy No. 2014-589)
November 4, 2015	Revised (Notification of the Ministry of Trade, Industry & Energy No. 2015-578)
January 8, 2016	Revised (Notification of the Ministry of Trade, Industry & Energy No. 2016-006)

March 9, 2016	Revised (Notification of the Ministry of Trade, Industry & Energy No. 2016-094)
October 19, 2016	Revised (Notification of the Ministry of Trade, Industry & Energy, No. 2016-545)
January 9, 2017	Revised(Notification of Ministry of Trade, Industry & Energy, No. 2017-3)
February 10, 2017	Revised (Notification of the Ministry of Trade, Industry & Energy No.2017-66)
February 28, 2019	Revised (Notification of the Ministry of Trade, Industry & Energy No. 2019-153)

Table of Contents

General.....	1
1. Scope.....	1
1.2 Validity of Code.....	1
1.3 Definitions.....	1
1.4 Application of Codes (currently not used).....	7
1.5 Interim Measures.....	7
1.5.1 Interim measure for thickness calculation and material of piping.....	7
1.5.2 Interim measure for installation of safety devices.....	8
1.5.3 Interim measure for protection walls.....	8
1.5.4 Interim measure for installation standard for water spray systems.....	9
1.5.5 Interim measure for standards for heat resistant construction of storage tanks and cooling sprinkler systems.....	9
1.5.6 Interim measure for standards for installation of, supply by and use of small tanks.....	9
1.5.7 Interim measure for installation of piping.....	11
1.5.8 Interim measure for installation standard for water sprinkler systems <Newly established January 3, 2011>.....	11
1.5.9 Interim measure for installation standard for underground storage tank rooms <Newly established on January 3, 2011>.....	11
1.5.10 Interim measure for reinforcing bar arrangement for storage tank rooms<Newly established on January 3, 2011>.....	12
1.5.11 Interim measure for safety valves <Newly established on January 3, 2011>.....	12
1.5.12 Interim measure for installation of boundary marking <Newly established on July 27, 2011>.....	12
1.5.13 Interim measure for installation of storage tanks <Newly established on July 27, 2011>.....	12
1.5.14 Interim measure for installation of sprinkler systems, etc.<Newly established on June 26, 2012>.....	13
1.5.15 Interim measure for materials of collecting pipe and detecting tube of storage tank room <Newly established on May 20, 2013>.....	14
1.5.16 Interim measure for calculation of overpressure safety device discharge quantity <Newly established on June 27, 2013>.....	14
1.5.17 Interim measure for distance between dispenser and road boundary<Newly established on October 31, 2013>.....	14

1.5.18 Interim measure for installation of water sprinkler systems <Newly established on October 06, 2014>	14
1.5.19 Interim measure for transfer and filling location for a vehicle-mounted tank<Newly established on November 4, 2015>	15
1.5.20 Interim measure for installation of sunlight generation facility<Newly established March 9, 2016>	15
1.5.22 Interim measure for coverage criteria for road<Newly established March 9, 2016>	15
1.6 Restriction on Use of Materials	15
2. Facility Standard.....	15
2.1 Layout standard	16
2.1.1 Distance from protected installations	16
2.1.2 Distance from naked lights.....	17
2.1.3 Distance from other facilities (currently not used).....	17
2.1.4 Distance from business place perimeter	17
2.1.5 Distance from road boundary <Newly established on October 31, 2013>.....	18
2.1.6 Distance from railroad (currently not used).....	18
2.1.7 Securement of open area (currently not used).....	18
2.1.8 Special case of distance from extension or modification area.....	19
2.1.9 Distance between safety zones (currently not used).....	20
2.1.10 Road connection standard.....	21
2.1.11 Reinforcement by approval authorities <Revised on July 27, 2011>	21
2.2 Foundation Standard	21
2.2.1 Soil survey.....	21
2.2.2 Foundation works.....	25
2.2.3 Fixing of storage tanks	27
2.3 Storage Facility Standard	31
2.3.1 Materials of storage facilities (currently not used).....	31
2.3.2 Construction of storage facilities	31
2.3.3 Installation of storage facilities	33
2.4 Gas Facility Standard.....	49
2.4.1 Materials of gas facilities	49
2.4.2 Construction of gas facility <currently not used>.....	49
2.4.3 Thickness and strength of gas facilities.....	49
2.4.4 Installation of gas facilities.....	49
2.4.5 Performances of gas facilities	50
2.5 Piping Standard.....	50

2.5.1 Piping materials.....	50
2.5.2 Configuration of piping systems (currently not used).....	53
2.5.3 Thickness of piping.....	53
2.5.4 Piping joints.....	55
2.5.5 Expansion/contraction absorption measures for piping.....	55
2.5.6 Insulation of piping.....	56
2.5.7 Installation of piping.....	57
2.5.8 Installation of associated piping facilities (currently not used).....	65
2.5.9 Performance of piping.....	65
2.5.10 Marking of piping systems <Revised on October 6, 2014>.....	65
2.6 Accident Prevention Facility Standard.....	69
2.6.1 Installation of overpressure safety devices.....	69
2.6.2 Installation of gas leak alarm and automatic shutoff systems.....	81
2.6.3 Installation of emergency shutoff devices.....	84
2.6.4 Installation of backflow prevention devices (currently not used).....	86
2.6.5 Installation of backfire prevention devices (not applicable).....	86
2.6.6 Installation of hazard monitoring and control devices (not applicable).....	86
2.6.7 Installation of accidental startup prevention devices(not applicable).....	86
2.6.8 Installation of explosion-proof electrical facilities.....	86
2.6.9 Installation of ventilation system.....	86
2.6.10 Installation of corrosion prevention systems.....	87
2.6.11 Installation of static eliminators.....	88
2.6.12 Installation of anti-toppling facilities.....	89
2.7 Damage Control Facility Standard.....	90
2.7.1 Installation of dikes.....	90
2.7.2 Installation of protection walls.....	93
2.7.3 Installation of sprinkler systems.....	96
2.7.4 Installation of detoxification facilities (not applicable).....	97
2.7.5 Installation of neutralization and transfer facilities (not applicable).....	97
2.7.6 Installation of wind indicators (currently not used).....	97
2.7.7 Installation of fire extinguishingsystems (currently not used).....	97
2.7.8 Installation of traffic systems (currently not used).....	97
2.7.9 Installation of temperature rise prevention devices.....	97
2.8 Associated Facilities Standard.....	97
2.8.1 Installation of measuring facilities.....	97
2.8.2 Installation of emergency power systems.....	98
2.8.3 Installation of communication systems.....	100

2.8.4 Installation of operation facilities.....	100
2.8.5 Installation of safety maintenance facilities	101
2.8.6 Installation of stable supply facilities.....	102
2.8.7 Installation of vent stacks.....	102
2.8.8 Installation of flare stacks.....	103
2.9 Marking Standard.....	104
2.9.1 Boundary markings and warning signs	104
2.9.2 Identification marking and danger signs (currently not used).....	109
2.9.3 Perimeter fences	109
3. Technical Standard.....	109
3.1 Safety Maintenance Standard.....	109
3.1.1 Maintenance of foundations (currently not used).....	109
3.1.2 Maintenance of storage facilities.....	109
3.1.3 Maintenance of gas facilities.....	113
3.1.4 Maintenance of piping systems.....	116
3.2 Manufacturing and Filling Standard.....	117
3.2.1 Preparation for manufacturing and filling	117
3.2.2 Manufacturing and filling operation	122
3.3 Inspection Standard	124
3.3.1 Inspection of overall installation	124
3.3.2 Inspection of foundations (currently not used)	127
3.3.3 Inspection of storage facilities	127
3.3.4 Inspection of gas facilities (currently not used).....	127
3.3.5 Inspection of piping systems (currently not used).....	127
3.3.6 Inspection of accident prevention facilities.....	127
3.3.7 Inspection of damage control facilities.....	128
3.3.8 Inspection of associated facilities	128
3.4 Repairs, Cleaning and Removal Standard.....	129
3.4.1 Preparation for repairs, cleaning and removal.....	129
3.4.2 Repairs, cleaning and removal works.....	130
3.4.3 Follow-up measures after repairs, cleaning and removal.....	131
4. Inspection Standard	132
4.1 Inspection Items.....	132
4.1.1 Safety confirmation	132
4.1.2 Completion inspection.....	133
4.1.3 Regular inspection <Revised on December 2, 2009>	133
4.1.4 Occasional inspection.....	135

4.1.5 Detailed safety diagnosis.....	135
4.1.6 Safety assessment.....	136
4.2 Inspection Methods.....	136
4.2.1 Safety confirmation <revised on January 3, 2011>	136
4.2.2 Completion inspection and regular inspection.....	138
4.2.3 Detailed safety diagnosis.....	146
4.2.4 Safety assessment.....	148
5. Temporary Storage Standard.....	148
5.1 Installation Standard	148
5.2 Maintenance Standard.....	149
5.3 Other Standards.....	150
Appendix A Standard for Installation of Safety Devices before March 8, 2005.....	151

Code for Facilities, Technology, Inspection, Safety Diagnosis and Safety Assessment for Filling of LP Gas in Small Cylinders

1. General

1.1 Scope

This Code applies to the facilities, technology, inspection, detailed safety diagnosis and safety assessment for the business of filling and supplying liquefied petroleum gas in small cylinders (small gas cylinders of which internal volume is less than one liter; hereinafter the same shall apply) in the filling business of liquefied petroleum gas in conformity to the Safety Control and Business Regulation of Liquefied Petroleum Gas Act (hereinafter referred to as "Act"), Article 5, Clause 1. <Revised on November 4, 2015>

1.2 Validity of Code

1.2.1 This Code has passed the deliberation and resolution by Gas Technical Standards Committee (Bill No. 2019-1, February 15, 2019) in conformity to the High Pressure Gas Safety Control Act (hereinafter referred to as "High Pressure Gas Act"), Article 33-2, in accordance with the Act, Article 45, Clause 2, has been approved by the Minister of Trade, Industry & Energy (Notification No. 2019-153 of the Ministry of Trade, Industry & Energy, February 28, 2019), and is valid and effective as the detailed standards in conformity to the Act, Article 45, Clause 1.

1.2.2 Conformity to this Code is deemed to conform to Table 4, No. 1 of the Enforcement Regulation of the Safety Control and Business Regulation of Liquefied Petroleum Gas Act (hereinafter referred to as "Enforcement Regulation") in accordance with the Act, Article 45, Clause 4. <Revised on November 4, 2015>

1.3 Definitions

The terms used in this Code are defined as follows: